

SUMMARY OF QUANTITIES

TRAFFIC CONTROL	CSBRG-0007-00(181)
TOTAL	LUMP SUM
GRADING COMPLETE	CSBRG-0007-00(181)
TOTAL	LUMP SUM

RIGHT OF WAY MARKERS
TOTAL 15 EACH

W-BEAM GUARDRAIL		
STATION RANGE	SIDE	FT
32+23.71 TO 33+23.71	RT	100.00
32+48.71 TO 33+23.71	LT	75.00
35+84.29 TO 36+59.29	RT	75.00
35+84.29 TO 36+84.29	LT	100.00
TOTAL		350.00

GUARDRAIL ANCHORAGE, TYPE 1
TOTAL 2 EACH

T-BEAM GUARDRAIL		
STATION RANGE	SIDE	FT
33+23.71 TO 33+44.36	LT	21.00
33+23.71 TO 33+44.36	RT	21.00
35+63.64 TO 35+84.29	LT	21.00
35+63.64 TO 35+84.29	RT	21.00
TOTAL		84.00

GUARDRAIL ANCHORAGE, TYPE 12
TOTAL 2 EACH

REINFORCED CONCRETE APPROACH SLAB, GA. STD. 9017R					
STATION RANGE	REINF. CONC. APPROACH SLAB (SY)	GA. STD. 9017J CONCRETE SPILLWAY TYPE 1 (EA)		15' SLOPE DRAIN PIPE (LF)	CLASS "A" CONCRETE FOR APRON (CY)
		LEFT	RIGHT		
33+14 TO 33+44	122	1	1	120	0.34
35+64 TO 35+94	122	1	1	100	0.34
TOTAL	244	2	2	220	0.68

SURFACING QUANTITIES							
ITEM	UNIT	MAINLINE	FLARE	APPROACH SLAB	AS DIRECTED BY ENGINEER	TOTAL	
RECYCLED ASPH CONC 9.5 MM SUPERPAVE, TYPE 1, GP 1 OR BLEND 1, INCL BITUM MATL & H LIME	TN	229.5	2.4	16.4	49.7	298.0	
RECYCLED ASPH CONC 19 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	TN	374.0	4.0	26.8	81.0	485.8	
RECYCLED ASPH CONC 25 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL	TN	935.0	9.9	66.9	202.4	1214.2	
GR AGGR BASE CRS, 8 INCH, INCL MATL	SY	3400.0	36.1		687.2	4123.3	
BITUM TACK COAT	GL	272.0	2.9	29.2	60.8	364.9	

GEORGIA
DEPARTMENT
OF
TRANSPORTATION

REVISION DATES

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: DISTRICT 4
SUMMARY QUANTITIES

SR 64 @ TEN MILE CREEK

DRAWING No.
06-001