

## SUMMARY OF QUANTITIES

TRAFFIC CONTROL	CSBRG-0007-00(182)
TOTAL	LUMP SUM
GRADING COMPLETE	CSBRG-0007-00(182)
TOTAL	LUMP SUM

RIGHT OF WAY MARKERS
TOTAL <span style="float: right;">16 EACH</span>

W-BEAM GUARDRAIL		
STATION RANGE	SIDE	FT
68+03.47 TO 69+03.47	RT	100.00
68+48.96 TO 69+23.96	LT	75.00
71+10.04 TO 71+85.04	RT	75.00
71+30.53 TO 72+30.53	LT	100.00
<b>TOTAL</b>		<b>350.00</b>

GUARDRAIL ANCHORAGE, TYPE 1
TOTAL <span style="float: right;">2 EACH</span>

T-BEAM GUARDRAIL		
STATION RANGE	SIDE	FT
69+03.47 TO 69+24.12	RT	21.00
69+23.96 TO 69+44.61	LT	21.00
70+89.39 TO 71+10.04	RT	21.00
71+09.88 TO 71+30.53	LT	21.00
<b>TOTAL</b>		<b>84.00</b>

GUARDRAIL ANCHORAGE, TYPE 12
TOTAL <span style="float: right;">2 EACH</span>

REINFORCED CONCRETE APPROACH SLAB, GA. STD. 9017R					
STATION RANGE	REINF. CONC. APPROACH SLAB (SY)	GA. STD. 9017J CONCRETE SPILLWAY TYPE 1 (EA)		15° SLOPE DRAIN PIPE (LF)	CLASS "A" CONCRETE FOR APRON (CY)
		LEFT	RIGHT		
69+07 TO 69+37	122	1	1	100	0.34
70+97 TO 71+27	122	1	1	120	0.34
<b>TOTAL</b>	<b>244</b>	<b>2</b>	<b>2</b>	<b>220</b>	<b>0.68</b>

SURFACING QUANTITIES							
ITEM	UNIT	MAINLINE	FLARE	APPROACH SLAB	AS DIRECTED BY ENGINEER	TOTAL	
RECYCLED ASPH CONC 9.5 MM SUPERPAVE, TYPE 1, GP 1 OR BLEND 1, INCL BITUM MATL & H LIME	TN	175.6	2.4	16.4	38.9	233.3	
RECYCLED ASPH CONC 19 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	TN	286.1	4.0	26.8	63.4	380.3	
RECYCLED ASPH CONC 25 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL	TN	715.3	9.9	66.9	158.4	950.5	
GR AGGR BASE CRS, 8 INCH, INCL MATL	SY	2601.0	36.1		527.4	3164.5	
BITUM TACK COAT	GL	208.1	2.9	29.2	48.0	288.2	

**GEORGIA**  
DEPARTMENT  
OF  
TRANSPORTATION

REVISION DATES


STATE OF GEORGIA  
DEPARTMENT OF TRANSPORTATION  
OFFICE: DISTRICT 4  
**SUMMARY QUANTITIES**

SR 64 @ FIVE MILE CREEK

DRAWING No.  
**06-001**