



- (A) RECYCLED ASPHALTIC CONCRETE 12.5 mm, SUPERPAVE, GP.2 ONLY, INCL. BITUM. MAT'L & H.LIME (165 LBS/SY)
- (B) RECYCLED ASPHALTIC CONCRETE 19 mm, SUPERPAVE, GP 1 OR 2, INCL. BITUM. MAT'L & H.LIME (220 LBS/SY)
- (C) RECYCLED ASPHALTIC CONCRETE 25 mm, SUPERPAVE, GP 1 OR 2, INCL. BITUM. MAT'L & H.LIME (440 LBS/SY)
- (D) 14" GRADED AGGREGATE BASE, INCL MAT'L
- (E) RECYCLED ASPHALTIC CONCRETE LEVELING, INCL. BITUM. MAT'L & H.LIME (AS REQUIRED)
- (F) RECYCLED ASPHALTIC CONCRETE 25 mm, SUPERPAVE, GP 1 OR 2, INCL. BITUM. MAT'L & H.LIME (660 LBS/SY)

SEE GDOT CONSTRUCTION DETAIL P-7 FOR SAFETY EDGE

GEORGIA
DEPARTMENT
OF
TRANSPORTATION

REVISION DATES	STATE OF GEORGIA DEPARTMENT OF TRANSPORTATION OFFICE: DISTRICT SIX ROAD DESIGN
TYPICAL SECTIONS	SR20 SR108
	DRAWING No. 05 -001