



- (A) RECYCLED ASPHALTIC CONCRETE 9.5 mm TP1, SUPERPAVE, ONLY, INCL. BITUM. MAT'L & H. LIME (110 LBS/SY)
- (B) RECYCLED ASPHALTIC CONCRETE 19 mm, SUPERPAVE, GP 1 OR 2, INCL. BITUM. MAT'L & H. LIME (220 LBS/SY)
- (C) RECYCLED ASPHALTIC CONCRETE 25 mm, SUPERPAVE, GP 1 OR 2, INCL. BITUM. MAT'L & H. LIME (275 LBS/SY)
- (D) 8" GRADED AGGREGATE BASE, INCL. MAT'L
- (E) RECYCLED ASPHALTIC CONCRETE LEVELING, INCL. BITUM. MAT'L & H. LIME (AS REQUIRED)

SEE ROADWAY PLANS FOR SUPERELEVATION RATES AND TRANSITIONS

SEE GDOT CONSTRUCTION DETAIL P-7 FOR SAFETY EDGE

GEORGIA
DEPARTMENT
OF
TRANSPORTATION

	REVISION DATES	STATE OF GEORGIA DEPARTMENT OF TRANSPORTATION OFFICE: DISTRICT SIX ROAD DESIGN
		TYPICAL SECTIONS
		SRI08, UPPERSWEETWATER MT. OLIVE & WHITE RELOCATION
		DRAWING No. 05 -002