

SUMMARY OF QUANTITIES

SOLID TRAF STRIPE, 5 IN. WHITE	
TOTAL	2160 LF
SOLID TRAF STRIPE, 5 IN. YELLOW	
TOTAL	2160 LF
RAISED PAVEMENT MARKERS, TP 1, YELLOW	
TOTAL	36 EACH

PREFORMED PLASTIC SOLID PVMT MKG, 8 IN, CONTRAST (BLACK-WHITE), TP PB	
TOTAL	440 LF
PREFORMED PLASTIC SOLID PVMT MKG, 8 IN, CONTRAST (BLACK-YELLOW), TP PB	
TOTAL	440 LF

SUMMARY OF HIGHWAY SIGNS

SR 64 @ TEN MILE CREEK

STATION	QTY.	SIDE	CODE	SIZE	HIGHWAY SIGNS TP 1 MATL		GALV STEEL POSTS TYPE 7 LIN FT	DELINEATORS		
					TYPE 3	TYPE 9		TYPE 1	TYPE 2 WHT (12 REFLECTORS EA)	TYPE 3
					SO FT	SO FT		EA	EA	EA
30+19.00	1	RT	WB-13	36" X 36"		9.00	14			
31+14.00	2	RT & LT	DELINEATOR (INCS. POST)						2	
32+14.00	2	RT & LT	DELINEATOR (INCS. POST)						2	
32+50.00	1	LT	WI-2R	30" X 30"		6.25	14			
33+14.00	2	RT & LT	DELINEATOR (INCS. POST)						2	
33+34.00	1	RT	I-3	48" X 24"		8.00	14			
35+74.00	1	LT	I-3	48" X 24"		8.00	14			
35+94.00	2	RT & LT	DELINEATOR (INCS. POST)						2	
36+94.00	2	RT & LT	DELINEATOR (INCS. POST)						2	
37+94.00	2	RT & LT	DELINEATOR (INCS. POST)						2	
37+97.00	1	RT	D10-1	10" X 8"		2 X 0.56 = 1.12	14			
38+89.00	1	LT	WB-13	36" X 36"		9.00	14			
TOTALS						41.4	84		12	

GEORGIA
DEPARTMENT
OF
TRANSPORTATION

REVISION DATES

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: DISTRICT 4
SUMMARY QUANTITIES

SR 64 @ TEN MILE CREEK

DRAWING No.
06-003