

## SUMMARY OF QUANTITIES

TEMPORARY EROSION CONTROL	
TEMPORARY GRASSING	
TOTAL	4 AC
MULCH	
TOTAL	64 TN
CONSTRUCTION EXITS	
TOTAL	2 EA
CONST & REMOVE TEMP SEDIMENT BARRIER - BALED STRAW	
TOTAL	937 LF
CONSTRUCT & REMOVE INLET SEDIMENT TRAP	
TOTAL	4 EA
MAINTENANCE OF TEMPORARY SILT FENCE, TYPE C	
TOTAL	2315 LF
MAINTENANCE OF SEDIMENT BARRIER - BALED STRAW	
TOTAL	469 LF
MAINTENANCE OF CONSTRUCTION EXITS	
TOTAL	2 EA
MAINTENANCE OF INLET SEDIMENT TRAP	
TOTAL	4 EA

TEMPORARY EROSION CONTROL (CONT'D)	
CONST & REMOVE TEMP PIPE SLOPE DRAIN	
TOTAL	380 LF
CONST & REMOVE ROCK FILTER DAMS	
TOTAL	10 EA
MAINTENANCE OF ROCK FILTER DAM	
TOTAL	10 EA
TEMPORARY SILT FENCE, TYPE C	
TOTAL	4630 LF
WATER QUALITY MONITORING AND SAMPLING	
TOTAL	10 EA
WATER QUALITY INSPECTIONS	
TOTAL	12 MO
4' BARRIER FENCE (ORANGE)	
TOTAL	1377 LF

PERMANENT EROSION CONTROL	
PERMANENT GRASSING	
TOTAL	4 AC
AGRICULTURAL LIME	
TOTAL	8 TN
FERTILIZER MIXED GRADE	
TOTAL	4 TN
FERTILIZER NITROGEN CONTENT	
	200 LB