

# SUMMARY OF QUANTITIES

SOLID TRAF STRIPE, 5 IN. WHITE	
TOTAL	1680 LF
SOLID TRAF STRIPE, 5 IN. YELLOW	
TOTAL	1680 LF
RAISED PAVEMENT MARKERS, TP 1, YELLOW	
TOTAL	28 EACH

PREFORMED PLASTIC SOLID PYMT MKG, 8 IN, CONTRAST (BLACK-WHITE), TP PB	
TOTAL	320 LF
PREFORMED PLASTIC SOLID PYMT MKG, 8 IN, CONTRAST (BLACK-YELLOW), TP PB	
TOTAL	320 LF

## SUMMARY OF HIGHWAY SIGNS

SR 64 @ FIVE MILE CREEK

STATION	QTY.	SIDE	CODE	SIZE	HIGHWAY SIGNS TP 1 MATL		GALV STEEL POSTS TYPE 7	DELINEATORS		
					TYPE 3	TYPE 9		TYPE 1	TYPE 2 WHT (12 REFLECTORS EA)	TYPE 3
					SO FT	SO FT	EA	EA	EA	
66+12.00	1	RT	W8-13	36" X 36"		9.00	14			
66+96.50	1	RT	DELINEATOR (INCS. POST)						1	
67+17.50	1	LT	DELINEATOR (INCS. POST)						1	
67+96.50	1	RT	DELINEATOR (INCS. POST)						1	
68+17.50	1	LT	DELINEATOR (INCS. POST)						1	
68+71.50	1	LT	W1-2L	30" X 30"		6.25	14			
68+96.50	1	RT	DELINEATOR (INCS. POST)						1	
69+12.00	1	RT	I-3	48" X 24"		8.00	14			
69+17.50	1	LT	DELINEATOR (INCS. POST)						1	
71+16.50	1	RT	DELINEATOR (INCS. POST)						1	
71+22.00	1	LT	I-3	48" X 24"		8.00	14			
71+37.50	1	LT	DELINEATOR (INCS. POST)						1	
72+16.50	1	RT	DELINEATOR (INCS. POST)						1	
72+37.50	1	LT	DELINEATOR (INCS. POST)						1	
73+16.50	1	RT	DELINEATOR (INCS. POST)						1	
73+37.50	1	LT	DELINEATOR (INCS. POST)						1	
74+22.00	1	LT	W8-13	36" X 36"		9.00	14			
<b>TOTALS</b>						<b>40.25</b>	<b>70</b>		<b>12</b>	

**GEORGIA**  
DEPARTMENT  
OF  
TRANSPORTATION

REVISION DATES

STATE OF GEORGIA  
DEPARTMENT OF TRANSPORTATION  
OFFICE: DISTRICT 4

**SUMMARY QUANTITIES**

SR 64 @ FIVE MILE CREEK

DRAWING No.  
**06-003**